

PUGET SOUND NAVAL SHIPYARD

CONFINED AQUATIC DISPOSAL OF CONTAMINATED AND UNSUITABLE MARINE SEDIMENTS


OU B Marine Remedial Action and
FY00 MCON Project P-338






Overview of the Project

- Combines Two Projects Under a Single Contract
- Dredge Volumes
 - 150,000 cy CERCLA
 - 340,000 cy MILCON
 - 350,000 cy Pit CAD
- Required to Minimize Operational Disruptions



Early Design Development

- Draft FS Alternatives
 - Nearshore CAD
 - Pit CAD “Offsite”
 - Prohibited by DNR on State Lands
- Preferred Alternative
 - Nearshore CAD
 - Subtidal Berm/Dike
 - Sand Cap
 - Create New Intertidal Habitat





- Performed Geotechnical Boring Program
- Results:
 - Very Soft Sediments
 - “Zero” Blow Count to Depth of 130 feet

FOSTER WHEELER ENVIRONMENTAL

PROJECT RAC II D.O. 67

DATE DRILLED 6/18/99

DRILLING COMPANY Holt Drilling

DRILLING METHOD Hollow Stem Auger (3.5" ID)

GEOLOGIST D.B. Jones

SAMPLING METHOD 2.5" ID Split Spoon/ Shelby Tube

BORING NUMBER B-12

BORING LOCATION PSNS Bremerton, south central Cad site






TIDE GAUGE 9.6' at 0750

TOTAL DEPTH 146.2 Feet

DEPTH TO MUCLINE 37.3' at 0750

MUCLINE ELEVATION 27.7 Feet MLLW


NORTH/EAST COORDS 205503 1189146

BLOCK COUNT	DEPTH	SAMPLES feet	SAMPLE NUMBER	% SAMPLE RETENTION	MOISTURE	GRAPHIC LOG	SOIL CLASS	DESCRIPTION AND REMARKS
NA		<input type="checkbox"/>	B12P50	100	MOIST /WET		ML	Shelby tube advanced 50 to 52' (B12P50). Same as previous description with interbeds of medium to fine sand up to 2" thick with clayey SILT.
	55							Some soft sediment deformation.
0	60	<input checked="" type="checkbox"/>	B12S60	100	WET		ML/CL	Split tube advanced 60 to 61.5' (B12S60) by weight of rod. Dark green to olive drab, wet, cohesive, plastic, very soft, clayey SILT interbedded with medium to very fine sand. Scattered coarse sand fragments in clayey silt. 5% organic, 5% fine sand, 90% silt/clay.
	65							
0	70	<input checked="" type="checkbox"/>	B12S70	100	WET			Split tube advanced 70 to 71.5' (B12S70) by weight of rod. Same as previous description. 5% organic, 5% fine sand, 90% silt/clay.
	75							
0	80	<input checked="" type="checkbox"/>	B12S80	100	WET/ MOIST			Split tube advanced 80 to 81.5' (B12S80) by weight of rod. Same as previous description. 5% organic, 5% fine sand, 90% silt/clay.
	85							
0	90	<input checked="" type="checkbox"/>	B12S90	100	WET/ MOIST			Split tube advanced 90 to 91.5' (B12S90) by weight of rod. Same as previous description. 5% organic, 5% fine sand, 90% silt/clay.
	95							
	100							Harder sand unit here. (98.5)



Nearshore CAD Design

- Soft Foundation Required:
 - Pre Excavation
 - Buttressing
 - Staged (2 yr) Construction for Consolidation
- Consequence was:
 - Unacceptable Delay
 - Costly Solution
 - Limited Capacity





CAD Design Development

- Issues w/ Nearshore CAD
 - Construction Time
 - MILCON **Required** a June 2000 Start
 - Limited Capacity
 - Costly
 - Loss of Habitat
- Develop Cost Model
 - Upland Disposal of Unsuitable MILCON of up to \$10M **Greater** than Pit Disposal

Was There a Better Way?

CAD Design Development


- Solution
 - Navy Has Fee Simple Ownership to Outer Harbor Line
 - Identify Pit CAD Alternative on Navy Property
 - DNR Issue Rendered Moot





Pit CAD Design Development



- First: Sized for
 - MILCON Unsuitable Volume
 - CERCLA Volume
- Second: Pit Surface Sediments Assumed Unsuitable for Open Water Disposal
- Solution: A Three Pit System
Sequential Excavation and Disposal





Pit CAD DMMP Sampling


- DMMP Process
 - Based on “Worst Case” Sizing of Pit or Close to 700,000 cy
- Required
 - 29 Samples 0-3 ft
 - 18 Samples 3-7, 7-18 ft
 - No Sampling below 18
 - Ran Chemical & Biological Tests on All
- Results
 - One 4,000 cy Surface Unit Failed






Final Pit CAD Design

- Criteria
 - Design had to Assume “Worst Case” Scenario
 - MILCON Resampled Able to Reduce Disposal Volume to 345,000 cy
- Concurrently Obtained OK for Beneficial Use of Over 85,000 cy for:
 - Stockpile for Final CAD Cap
 - Nearshore Habitat Enhancement & CERCLA Cap





Pit CAD Construction Phase

- Subcontract Evaluation/Selection Process Initiated
 - General Construction Selected 
- Equipment mobilized
 - DB Los Angeles - 225 ton - 25 cy environmental bucket
 - DB Seattle - 165 ton - 24 cy environmental bucket
 - DB Olympia - 80 ton - APE 200 vibratory hammer
 - DB Tacoma - 37 ton - 4.5 cy clamshell bucket
 - 3 split-hull bottom dump barges
 - 2 flat deck barges
 - 2 tug boats
 - 1 bathymetric survey/water quality monitoring work boat
 - office trailers



Other Concurrent Approvals

- ARARS with
 - State Fish and Wildlife
 - Ecology
 - EPA
- Endangered Species Act (ESA)
 - Prepared Biological Assessment
- Tribes

Pit CAD Construction





Pit CAD Construction





Pit CAD Progress Surveys





Survey and Water Quality Monitoring




- Daily Bathymetric Surveys
- Extensive Water Quality Monitoring
 - In Situ STD, Oxygen, Turbidity
 - Current Profiling
 - Chemical Analysis
- Pre Dredge Side Scan for Debris/Gas Cylinders





Remediation Progress Surveys





Where Are We Now?

Where Are We Headed?

- Pit CAD Completed on August 15th
- CERCLA Dredging Underway
- MILCON Dredging Underway
- On Schedule to Complete Dredging by February, 2001
- Place Interim CAD Sand Cap by March 15, 2001
- Allow Pit to Consolidate During Fisheries Closure
- Complete CAD Cap in July, 2001



Working Together for a Successful Project